Job Name/Location: For: File Resubmit Date: Approval Other\_ PO No .: GC: Architect: Mech: Engr: Rep:

(Project Manager)

**LG** 

## LMVN240HV

Multi F 2-Way Vertical/Horizontal Air Handling Unit

(Company)

#### Performance:

Nominal Cooling Capacity (Btu/h)	24,000
Nominal Heating Capacity (Btu/h)	27,000

Heating Nominal Test Conditions: Cooling Nominal Test Conditions: Indoor: 80°F DB / 67°F WB Indoor: 70°F DB / 60°F WB Outdoor: 95°F DB / 75°F WB Outdoor: 47°F DB / 43°F WB

## **Electrical:**

Power Supply (V¹/Hz/Ø)	208-230/60/1
Rated Amps (A)	0.59

## Piping:

Installed Liquid Pipe (in., O.D.)	ø1/4
Installed Vapor Pipe (in., O.D.)	ø1/2
Liquid Connection (in., O.D.)	ø1/4
Vapor Connection (in., O.D.)	ø1/2
Drain (in., O.D. / I.D.)	3/4 FPT
Temperature Sensor	Thermistor

#### **Standard Features:**

• Access Panel for Field Supplied Air Filter (16 x 20 x 1 inch)

#### **Controls Features:**

 ESP Control Hot Start

Auto Restart

- Group Control
- Sleep Mode
- Timer On / Off
- · Controller Sold Separately Child Lock
- Inverter (Variable Speed Fan)

## **Optional Accessories:**

- ☐ Simple Remote Controller PREMTC00U ☐ MultiSITE™ CRC1 Controller - PREMTBVC0 ☐ MultiSITE™ CRC1+ Controller - PREMTBVC1
- ☐ Premium Remote Controller PREMTA000
- ☐ Wireless Handheld Remote Controller PQWRHQ0FDB<sup>2</sup>
- ☐ AC Smart 5 PACS5A000
- ☐ ACP 5 PACP5A000
- ☐ LonWorks Gateway PLNWKB100
- ☐ AC Smart IV BACnet PBACNA000
- ☐ ACP IV BACnet Gateway PQNFB17C2
- ☐ Dry Contact (1 contact, 24 VAC external power) PDRYCB100
- ☐ Dry Contact for Third Party Thermostat PDRYCB300
- ☐ Dry Contact for (2 setpoints) PDRYCB400
- ☐ Remote Temperature Button Sensor ZRTBS01
- ☐ 5 kW Electric Heater ANEH053B1
- ☐ 10 kW Electric Heater ANEH103B2

## **Entering Mixed Air:**

Tag #:

Cooling (°F DB)	57 ~ 77
Heating (°F WB)	59 ~ 81

## **Unit Data:**

Refrigerant Type	R410A
Refrigerant Control	EEV
Sound Pressure (H/M/L) dB(A) <sup>3</sup>	43 / 42 / 41
Net Weight (lbs.)	117
Shipping Weight (lbs.)	130

#### Fan:

Туре	Sirocco
Quantity	1
Motor/Drive	Brushless Digitally Controlled/Direct
Air Flow H/M/L (CFM)	710 / 640 / 480
External Static Pressure <sup>4,5</sup> (in wg)	0.5
Minimum External Static Pressure <sup>6</sup>	0.1
Maximum External Static Pressure <sup>6</sup>	1.0

## Notes:

- Acceptable operating voltage: 187V-253V.
   Requires an LG wired thermostat.
- 3. Sound Pressure levels are tested in an anechoic chamber under ISO Standard 3745
- Adjust fan speed to correct for static pressure increases when using field-supplied air filter.
   At factory fan speed setting.
   Air flow rate (CFM) at high speed.

- 6. Air flow rate (CFM) at high speed.
  7. See Engineering Manual for sensible and latent capacities.
  8. All communication / connection (power) cable from the outdoor unit to the indoor unit is field supplied and must be a minimum of four-conductor, 18 AWG, stranded, shielded or unshielded (if shielded, it must be grounded to the chassis of the outdoor unit only), and must comply with applicable local and national codes.
  9. Power wiring cable size must comply with the applicable local and national code.
  10. The indoor unit comes with a dry helium charge.
  11. Corresponding refrigerant piping length is in accordance with standard length of each outdoor unit and the level difference is 0 ft. All capacities are net with a combination ratio between 95 105%.
  12. Must follow installation instructions in the applicable (is installation manual).

- 12. Must follow installation instructions in the applicable LG installation manual.







Job Name/Location:

# LMVN240HV Multi F 2-Way Vertical/Horizontal Air Handling Unit



Tag No.: \_\_\_\_\_\_

PO No.:

